








PLANTING PLAN

TREES	BOTANICAL / COMMON NAME	CONT	QTY	
	ACER TATARICUM / TATARIAN MAPLE	2" CAL	3	
	PINUS PONDEROSA / PONDEROSA PINE	5`-6` TALL	9	
	QUERCUS GAMBELII / GAMBEL OAK	2" CAL	16	
SHRUB AREAS	BOTANICAL / COMMON NAME	CONT	SPACING	QTY
	ARCTOSTAPHYLOS X COLORADOENSIS `PANCHITO` / PANCHITO MANZANITA	1 GAL	48" o.c.	71
	CHRYSOTHAMNUS NAUSEOSUS NAUCEOSUS / DWARF BLUE RABBITBRUSH	1 GAL	36" o.c.	180
	RHUS AROMATICA `GRO-LOW` / GRO-LOW FRAGRANT SUMAC	1 GAL	72" o.c.	57
GROUND COVERS	BOTANICAL / COMMON NAME	CONT	SPACING	QTY
	SEED	SEED		10,754 SF
<div>— — —</div> LIMIT OF WORK				

GENERAL NOTES

1. THE CONTRACTOR SHALL OBTAIN, AT THEIR OWN EXPENSE, APPLICABLE LICENSES, STANDARDS, PERMITS, ETC. WHICH ARE NECESSARY TO PERFORM THE WORK.
2. THE CONTRACTOR SHALL LOCATE, CLEARLY MARK AND MAINTAIN EXISTING UTILITIES ON THE SITE PRIOR TO WORK START UP. CALL FOR UTILITY LOCATES PRIOR TO COMMENSING WORK.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND REPAIR OF UTILITIES IF DAMAGED. REPAIR SHALL BE DONE AT NO ADDITIONAL COST TO THE OWNER
4. ALL DIMENSIONS SHALL BE FIELD VERIFIED BY CONTRACTOR PRIOR TO CONSTRUCTION. ANY DEVIATION FROM THESE PLANS MUST BE APPROVED BY OWNER OR LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION.
5. LIMIT OF WORK IS AS INDICATED ON THE PLANS.
6. COORDINATE SITE ACCESS, STAGING, STORAGE AND CLEANOUT AREAS WITH OWNER'S REPRESENTATIVE.
7. CONTRACTOR TO PROVIDE SIGN THAT TRAIL IS UNDER CONSTRUCTION, BOTH SIDES OF CONNECTION APPROX 100' FROM CONNECTION.
8. CONTRACTOR TO PROVIDE ONE PERSON AS A SAFETY WATCH IF ANY HEAVY EQUIPMENT IS BEING USED ON OR ADJACENT TO THE EXISTING IN USE TRAIL.

PLANTING NOTES

1. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL PLANT QUANTITIES. GRAPHIC QUANTITIES TAKE PRECEDENCE OVER WRITTEN QUANTITIES.
2. ALL LANDSCAPE AREAS SHALL RECEIVE SOIL PREPARATION AS SPECIFIED.
3. ALL EXISTING GRASS STAND AREAS DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE SOIL PREPARED AND SEEDDED BY THE CONTRACTOR.
4. EXISTING SEEDDED AREAS SHALL BE RESEEDDED AFTER CONSTRUCTION, TO INCLUDE ALL DISTURBED AREAS, CONSTRUCTION, GRADING AND PAVING OPERATION AREAS AND LAYDOWN AREAS SHALL ALSO BE RESTORED.
5. ALL LANDSCAPE MATERIALS SHALL BE INSTALLED ACCORDING TO SOUND HORTICULTURAL PRACTICES AND AMERICAN NURSERY STANDARDS IN A MANNER DESIGNED TO ENCOURAGE QUICK ESTABLISHMENT AND HEALTHY GROWTH.
6. REPAIR DISTURBED AREAS BENEATH SHRUBS BY HAND.
7. REPAIR AND RESEED STAGING AREA.
8. CONTRACTOR SHALL COORDINATE IRRIGATION AND PLANTING WORK SUCH THAT INSTALLED IRRIGATION EQUIPMENT SHALL NOT CAUSE ADJUSTMENT OF PLANTING LOCATIONS CONTRARY TO THE PLANS. IF IRRIGATION EQUIPMENT IS INSTALLED IN LOCATIONS OBSTRUCTING THE INTENDED LOCATIONS OF THE PLANTINGS, NOTIFY THE LANDSCAPE ARCHITECT FOR CLARIFICATION.
9. THE CONTRACTOR SHALL WARRANTY ALL CONTRACTED WORK AND MATERIALS FOR A PERIOD OF ONE YEAR AFTER SUBSTANTIAL COMPLETION HAS BEEN ISSUED BY THE OWNER'S REPRESENTATIVE FOR THE ENTIRE PROJECT UNLESS OTHERWISE SPECIFIED IN THE CONTRACT DOCUMENTS OR SPECIFICATIONS.
10. POCKET PLANT ALL TREES, SHRUBS AND GROUND COVERS AS PER DETAILS.
11. AREAS TO BE SEEDDED OR SODDED TO BE AMENDED WITH A MIN. 6" DEPTH TOP QUALITY TOPSOIL PRIOR TO SEEDING OR SODDING.



PLANTING PLAN

SCALE: 1" = 30'



GALLATIN COUNTY
STATE OF MONTANA

17092_02_LS_Trail.dwg
10/23/2020
3:45 PM BMB/CMK

DESIGNED BY BMB/CMK/JS/NL/JMC
REVIEWED BY TRP/DS/MLF/DJC
CHECKED BY TRP/DS/MLF/DJC

PLANTING PLAN


GALLATIN COUNTY, MADISON COUNTY

FOR BIDDING

MONTANA HIGHWAY 64 (LONE MOUNTAIN TRAIL)

SANDERSON STEWART

L1




NOTES:

1. REMOVE NURSERY STAKES.
2. PRUNE DEAD OR DAMAGED LIMBS IMMEDIATELY AFTER PLANTING.
3. REMOVE WIRE TIES AND BURLAP FROM ROOT BALL
4. PRIOR TO MULCHING, LIGHTLY TAMP SOIL AROUND ROOT BALL IN 6" LIFTS TO BRACE TREE. DO NOT OVER COMPACT. WHEN PLANTING PIT HAS BEEN BACKFILLED, POUR WATER AROUND ROOT BALL TO SETTLE THE SOIL.
5. REMOVE STAKES FOLLOWING FIRST GROWING SEASON.
6. SCARIFY SUBGRADE 12", RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.

1

DECIDUOUS TREE

N.T.S.




NOTES:

1. REMOVE NURSERY STAKES.
2. PRUNE DEAD OR DAMAGED LIMBS IMMEDIATELY AFTER PLANTING.
3. REMOVE WIRE TIES AND BURLAP FROM TOP 1/2 OF ROOT BALL.
4. PRIOR TO MULCHING, LIGHTLY TAMP SOIL AROUND ROOT BALL IN 6" LIFTS TO BRACE TREE. DO NOT OVER COMPACT. WHEN PLANTING PIT HAS BEEN BACKFILLED, POUR WATER AROUND ROOT BALL TO SETTLE THE SOIL.
5. REMOVE STAKES FOLLOWING FIRST GROWING SEASON.

2

CONIFEROUS TREE

N.T.S.




NOTES:

1. SHRUBS WITH BROKEN OR CRUMBLING ROOT BALLS WILL BE REJECTED. CONTAINER REMOVAL WILL NOT BE AN EXCUSE FOR DAMAGED ROOT BALLS.
2. TOP OF MULCH TO BE 1" BELOW ADJ WALKWAY, CURB, EDGING, OR OTHER SURFACE.
3. PRUNE OUT ALL DAMAGED OR DEAD WOOD.
4. ALL PLANT MATERIAL TO BE INSPECTED UPON DELIVERY. REJECTED MATERIALS TO BE IMMEDIATELY RETURNED TO SOURCE.
6. SCARIFY SUBGRADE 12", RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.

3

SHRUB PLANTING

N.T.S.




NOTE:

1. SCARIFY SUBGRADE 12", RAKE SUBGRADE AND REMOVE ALL DEBRIS GREATER THAN 1/2" IN DIA. INCLUDING ROCKS, CONCRETE, ORGANIC DEBRIS, AND OR CONSTRUCTION DEBRIS.

4

SEEDING

N.T.S.



5

PERENNIAL/GRASS/GROUNDCOVER SPACING

N.T.S.



GALLATIN COUNTY
STATE OF MONTANA

17092_02_LS_DETAILS.dwg
10/23/2020
3:45 PM BMB/CMK

DESIGNED BY BMB/CMK/JS/NL/JMC
REVIEWED BY TRP/DS/MLF/DJC
CHECKED BY TRP/DS/MLF/DJC

PLANTING DETAILS

GALLATIN COUNTY, MADISON COUNTY

FOR BIDDING

MONTANA HIGHWAY 64 (LONE MOUNTAIN TRAIL)

SANDERSON STEWART

L2